

POWER PROFILE

OCCIDENTAL MUKHAIZNA

RENTAL POWER PROJECT

- 9.28 MW installed power.
- Extensive distribution of Power at 11KV and 415V.
- Uninterrupted Power required to keep RO plant operating.
- 24 x 7 Operation & Maintenance and Fuel Management.
- Remote site location.
- Equipment: 2 x 3516B, 3 x 3512B, 3 x C32 gensets, 10 x 1.6 – 3.5 MVA Transformers.



CUSTOMER

Occidental Mukhaizna

LOCATION

Muscat

CUSTOMER BUSINESS ISSUE

Power required for Reverse Osmosis Plant and associated lighting loads.

SOLUTION

9.2 MW Prime Power.

DURATION

18 months

CAT DEALER

OTECO, Muscat